structural

Engineering Servicing Report for LandCorp on Cockburn Central West pritchard francis

providing the right solution



Level 1 430 Roberts Road PO Box 2150 Subiaco WA 6904

Telephone: (08) 9382 5111

Facsimile: (08) 9382 5199 admin@pfeng.com.au

Job No: 12-251

Engineering Servicing Report

for

LandCorp

on

Cockburn Central West

April 2013

Revision	Description	Date
0	Issued for input into the Local Structure Plan	19 April 2013
1	Amended and Reissued for Local Structure Plan	1 May 2013

Document Set ID: 5552576 Version: 1, Version Date: 03/02/2017



Table of Contents

	Table of Contents	Ī
1 Introduction		
2 Landform and Soils		3
2.1	Existing Site Conditions	3
2.2	Geology	3
2.3	Topography	3
2.4	Earthworks and Retaining Walls	4
3 Ground Water and Surface Water 5		
3.1	Groundwater Levels	5
3.2	Surface Water	5
4 Proposed Infrastructure		6
4.1	Stormwater Drainage	6
4.2	Sewer Reticulation	6
4.3	Water Reticulation	6
4.4	Gas Supply	7
4.5	Electrical Supply	7
4.6	Communications	7
4.7	Parking	8
4.8	Staging	8
5 Conclusion 10		
	Appendices	
Appendix A: Preliminary Earthworks Plan		
Appendix B: Water Corporation Dial-Before-You-Dig		

Appendix C: ATCO Gas Dial-Before-You-Dig Plans

Appendix D: Dial-Before-You-Dig Western Power



1 Introduction

At the request of LandCorp, Pritchard Francis Pty Ltd has prepared this report to determine the engineering opportunities and constraints for the development of Cockburn Central West.

The landholding has an area of approximately 32.8 hectares bound by North Lake Road to the north, Beeliar Drive to the south, Poletti Road to the west and Midgegooroo Avenue to the east. The site is located to the west of the existing Cockburn Central Town Centre and Cockburn Train Station and comprises of:

- Lot 1 North Lake Road, Cockburn Central.
- Lot 53 North Lake Road, Cockburn Central.
- Lot 54 Poletti Road, Cockburn Central.
- Lot 55 North Lake Road, Cockburn Central.
- Lot 804, Beeliar Drive, Cockburn Central.
- Lot 1001 Beeliar Drive, Cockburn Central.
- Lot 9504 Beeliar Drive, Cockburn Central.

The following report is based on the Activity Centre Structure Plan (P5002 - STR02, Rev C), shown in Figure 1.2 prepared by Cardno on 28 February 2013.

The following sections contain the findings from desktop investigations of existing services, opportunities and constraints associated with the development of residential lots in the landholding which is shown below in Figure 1.1.



Figure 1.1: Aerial photograph of the site





Figure 1.2: Activity Centre Structure Plan – Plan 1

12-251 Cockburn Central West Page 2



2 Landform and Soils

2.1 Existing Site Conditions

The current site is vacant of any built structures and contains many mature trees and vegetation, majority of which will have to be removed to allow for the proposed development of the site. There is an existing wetland on the site, however it is our understanding that the wetland is of low retention value.

On the western side of the landholding is a Western Power Easement, with 330kV transmission lines running parallel to Poletti Road. Any works undertaken in this easement will require liaison and approval from Western Power and any proposed infrastructure will require specials investigations to be carried out to determine whether they are suitable for construction in the easement.

On the northern side of the landholding is an ATCO High Pressure Gas Easement parallel to North Lake Road. There is also an open drain running south of North Lake Road which currently conveys 100 year floods in the region.

2.2 Geology

Geological conditions vary over the site. A review of the 1:50 000 Environmental Geology Series maps of Fremantle indicate the site consists of:

- Sand Well drained when dry and vegetation free, with drainage disposal only a problem in areas with a high groundwater table.
- Sand over silt and clay Sand layers are of variable thickness and properties are modified by the underlying material. These areas generally have a high water table and are prone to flooding.
- Sandy silt High water table, prone to flooding, differential settlement may occur.

A review of the map indicates predominately sand in the higher areas and sandy silt in the low lying areas. Sandy areas are of higher permeability than the sandy silt areas. It is recommended that a detailed site specific geotechnical investigation be undertaken by a certified geotechnical engineer to confirm site conditions and the geological development constraints. This will allow better planning for the site area and ensure maximum utilisation of material is achieved.

2.3 Topography

The levels on the site vary from RL 40.0m, along Beeliar Drive to the south of the landholding to RL 22.75m at the base of the wetland area located on the eastern boundary of the landholding. The site grades steeply on the south east corner as the levels transition from the higher levels on Beeliar Drive to the low lying wetland.

Design levels on the site are constrained where access into Cockburn Central West is proposed at Poletti Road, Midgegooroo Avenue and North Lake Road. Where no access for vehicles is to be provided from the existing roads, particularly Beeliar Drive and portions of Poletti Road, there is potential to amend levels and batter or install retaining walls to accommodate level differences, while ensuring levels are not too far below existing road levels to retain



commercial exposure of future developments. Lowering of the lots will reduce the imported fill required onto the site while providing a screening from the industrial area to the west.

A site specific survey will be required to be undertaken by a certified surveyor prior to construction to confirm the existing site levels, for both this land, surrounding areas and tie-in points.

2.4 Earthworks and Retaining Walls

Importation of fill will be required to create a site suitable for development. Where possible the proposed design level will integrate with the existing topography, grading higher lying ground on the southern side of the site down to tie in with the lower levels at the proposed basin on the north east of the site. Design levels of lots are to be set with an appropriate clearance to groundwater levels, typically 1.5m. Please refer to the attached Preliminary Earthworks Plan in Appendix A for details of approximate road levels.

Retaining walls are proposed on the southern side of the main oval to integrate the levels of the higher ground adjacent to Beeliar Drive with the proposed design levels of the oval.

Consideration should be given to minimise import of fill required by battering into the development as well as grading of parcels of land to better suit the natural topography of the area. As there is a high level of building articulation, with buildings addressing both roads and public open spaces, the lots can be stepped, with people entering one or two storeys above on the higher side of the development lot.



3 Ground Water and Surface Water

3.1 Groundwater Levels

The Department of Water's Ground Water Atlas indicates that the water table sits at RL 24-25 based on historical maximum ground water levels. In lower lying areas of the development, fill will be required to provide sufficient clearance between building pads and the groundwater table. Based on the current requirements this level will be 1.5m above the maximum groundwater table.

Site conditions will need to be confirmed by an environmental consultant and geotechnical engineer prior to any detailed design.

3.2 Surface Water

Surface water will be collected in the roadway drainage systems by using pits and pipes for storm events up to 5 years. For storm events in excess of 5 years, stormwater will traverse through the site using overland flow paths with an outfall into an existing drain, on the southern side of North Lake Road, once 1 in 10 year storm capacity has been reached.



4 Proposed Infrastructure

4.1 Stormwater Drainage

This project will be designed and documented in accordance with all relevant standards and codes of practice related to the design requirements of this project, but in general will be governed by the Australian Rainfall and Runoff Guidelines 2001, and Australian Runoff Quality 2006 as well as the City of Cockburn's requirements.

Post development residential and commercial lots stormwater drainage can be managed via localised soakwells, where the ground condition permits, however will be minimised as much as possible. Stormwater runoff from road reserves will be conveyed into designated areas, via pit and pipe systems. A stormwater drainage basin will be located on the North East side of the site. It is intended that the existing wetland be filled and developed. The majority of the sites stormwater shall be directed to the proposed basin however a small portion of the higher ground shall be collected in Parcel 11. The size and location of this drainage basin will be determined at detailed design stage.

The stormwater strategy will be dependent on the geological conditions on the site as well as the contributing catchment to the drainage basin located onsite. The detailed design will be carried out in accordance with the Urban Water Management Plan (UWMP) and Local Water Management Strategy (LWMS) at detailed design stage. Consideration will also be given to Water Sensitive Urban Sensitive Design (WSUD) and further investigation into methods of treatment of stormwater at source. Pit and pipe stormwater drainage shall be minimised as much as possible. Any stormwater drainage employed on site shall also manage flood and inundation risks by providing adequate clearance from 1 in 100 ARI flood levels.

4.2 Sewer Reticulation

Water Corporation Dial-Before-You-Dig plans have been obtained and are attached in Appendix B of this report. The plans show that there is an existing 225mm PVC sewer main in North Lake Road to the north of the proposed development, as well as 225mm PVC sewer in Poletti Road to the west of the landholding.

Pritchard Francis has made contact with the Water Corporation who have advised that the site is situated in the Water Corporation's Jandakot Sewer District. No wastewater infrastructure is presently on the site and therefore will need to be planned, designed and built to service the development. Water Corporation's planning assumes that the site will be gravitated towards the 500mm sewer that presently terminates at the intersection of North Lake Road and Polletti Road near the north west corner of the site.

The Water Corporation have also advised that they are due to review its planning for this area in the next year or two. This review will need to assess the cumulative impact of the Cockburn Central West Development to determine whether further headworks upgrades will be required in the future. Further liaison with the Water Corporation will be required during detailed design to confirm servicing and resolve any upgrades required.

4.3 Water Reticulation

Water Corporation Dial-Before-You-Dig plans have been obtained and are attached in Appendix B of this report. These plans show that there are existing water mains surrounding the development. It is anticipated that water will be



provided to the proposed subdivision via the interconnection of the existing 400mm main in Poletti Drive and the 150mm main in Midgegooroo Avenue.

Pritchard Francis has made contact with the Water Corporation who have advised the Corporation's long term planning appears to have made allowance for servicing this land from the surrounding distribution network. They have advised that it is likely that reticulation mains can be extended to at least serve the initial stages of the development. However, in the absence of up to date water scheme planning they will not provide advice on how much of the development can be served or what upgrades, if any are required.

Water Corporation Planning Engineers are currently undertaking a capacity review of the Thompson Lake Water Scheme which will lead to a full scheme review in the next one or two years. This review will determine if additional distribution mains or system upgrades are required to service this development. Further liaison with the Water Corporation will be required during the detailed design stage of the development when they will hopefully have more information.

4.4 Gas Supply

Dial-Before-You-Dig plans have been received from ATCO Gas and are attached in Appendix C of this report. The plans show existing gas reticulation surrounding the proposed development, as well as 300mm high pressure main running through the site parallel to North Lake Road on the northern boundary of the site. A 17.5m exclusion zone from the high pressure gas main to any structures will be created along the sites northern boundary as shown on the structure plan. Pritchard Francis has contacted ATCO Gas and have received confirmation that the existing infrastructure can serve the proposed development.

4.5 Electrical Supply

Western Power's Dial-Before-You-Dig plans have been obtained and are attached in Appendix D of this report. Western Power's Network Capacity Mapping indicates that there is capacity available in the area. We anticipate that as part of the development additional switchgears and transformers will be required to reinforce the network to allow for the high density expansion of the area.

The existing overhead power lines running parallel to Midgegooroo Avenue will be required to be undergrounded as part of the development work to make way for the proposed development. Liaison will be required with Western Power at the detailed design stage for this work to be co-ordinated.

Existing overhead high voltage power lines protected by an easement running parallel to Poletti Road will be remaining in place and any work in the power line easement will have to be separately negotiated with Western Power.

4.6 Communications

It is anticipated communication will be provided to the site by NBN Co as a development of this site fits in with the criteria for providing service to the site. An application will be made to NBN Co at the detailed design stage to confirm this. Until this application is made NBN Co will not provide any information.



4.7 Parking

Parking is to be predominantly designated short term parking spaces, located within the Western Power easement as well as short term parking surrounding the ovals. Parking surrounding the ovals is to be short term in nature and for visitors of residents, businesses within the area and recreational users.

Western Power is currently in the process of undertaking line surveys and clearances calculations that will provide constraints for the design of parking under these transmission lines and a report will be issues by Western Power. Norman Disney Young have also been commissioned to undertake EMF, EPR and LFI studies for the power lines.

4.8 Staging

Stage 1 Forward Works

During Stage 1, necessary earthworks will be carried out including stripping topsoil from entire site, over excavating playing fields to bury topsoil and cut to fill necessary for the early stages of works. Pending Western Power approval, fill from the Western Power easement will be cut for use as fill elsewhere on site.



Figure 4.1: Stage 1

Stage 1A - Civil Works for Oval and Community Facilities

This stage of works will include construction of roads, drainage, extension of services to the site from existing infrastructure located North West of the site on North Lake Road, earthworks, retaining walls and other works associated with development of the main oval and support precinct area. Pending Western Power approval, carparks located within the Western Power easement will be constructed.




Figure 4.2: Stage 1A



Stage 1B - Civil Works for POS Drainage

This stage of works will include civil works such as roads, drains, sewer, water, power, gas, communication and infrastructure required to service the proposed POS drainage area and playing fields. Works will also include servicing for lots being released in this stage.




Figure 4.3: Stage 1B

Stage 2, 3A – 3C – Development Release – Vision Completion

Civil works including the provision of water, sewer, roads, drains, walls and authority services required to release these stages will be undertaken. Completion of earthworks will be undertaken as required.







Figure 4.4: Stage 2

Figure 4.5: Stage 3A & 3B

Figure 4.6: Stage 3C



5 Conclusion

This report confirms that the proposed development is capable of being served with all of the essential services. Based on the information available at the time of this report, geological conditions of the site should not present any constraints to the development, however a geotechnical investigation will be required to confirm this.

Confirmation will be required from service authorities at detailed design stage on the actual capacities of existing infrastructure and any upgrades that may be required to serve the proposed subdivision. Further surveys and geotechnical investigations will be required prior to any detailed design and commencement of any construction work on site.



Appendices

Appendix A: Preliminary Earthworks Plan

Appendix B: Water Corporation Dial-Before-You-Dig


Appendix C: ATCO Gas Dial-Before-You-Dig Plans

Appendix D: Dial-Before-You-Dig Western Power



Appendix A: Preliminary Earthworks Plan


Document Set ID: 5552576 Version: 1, Version Date: 03/02/2017







Appendix B: Water Corporation Dial-Before-You-Dig

Document Set ID: 5552576 Version: 1, Version Date: 03/02/2017








Version: 1, Version Date: 03/02/2017




Version: 1, Version Date: 03/02/2017












08/10/2012 Page: 7 of 8


Water










Version: 1, Version Date: 03/02/2017






Version: 1, Version Date: 03/02/2017








Document Set ID: 5552576 Print Date:
Version: 1, Version Date: 03/02/2017

08/10/2012 Page: 7 of 8

Sewer





Appendix C: ATCO Gas Dial-Before-You-Dig Plans

Document Set ID: 5552576 Version: 1, Version Date: 03/02/2017


WARNING -HIGH PRESSURE PIPELINE IN THE VICINITY. No excavations within 15 metres of this asset are permitted without prior approval from ATCO Gas Australia PH 1300 926 755 Overview Map Only 12 © 2011 ATCO Gas Australia Pty Ltd Map Tile: Overview Scale: 1:7,502 Sequence No:26632715 ACN 089 531 975 5809714 09/10/2012 Location: N Lake Rd Job No: Date: Please read all warnings, conditions and information on the attached "Underground Asset Details" information sheet. This plan is issued subject to that information and those conditions and warnings (including, but not limited to, the "NO HOT WORKS" warning). Plans are current for only © 2011 Western Australian Land Information Authority trading as Landgate


Based on information provided by and with the permission of the


Western Australian Land Information Authority trading as Landgate


30 days from date of request, indicative only and not warranted to be accurate. It is your responsibility to carefully locate underground assets


dendrice was a few was a f




































Appendix D: Dial-Before-You-Dig Western Power



3፱øፀም24"\$ (Zone 50): (39166212,644530241) Scale: 1:2500 Profile: #DBYD (Modified)

User: n041037

Cable Joint Ces Scheme Join Underground Easements Join **Water Feature** Tee Junction Oil Pipe Carrier Approximation Otc Underground Cable Lodged Centroids Data Overhead Data Underground Planned Subdivisions **Turquoise Precalc Centroids** Kiosk ****** L. V. Distribution Frame Turquoise Precalc Int Lot Boun **Turquoise Precalc Road Front** Pillar Ring Main Unit **Green Legal Centroids** Substation **Obsolete Centroids Underground Crossing** St. Lt. Pilot, Overhead St. Lt. Pilot, Underground Fuse Disconnector, Overhead St. Lt. Circuit, Overhead St. Lt. Circuit, Underground Distribution Pipe Link Pipe Trunk Pipe Bright Conduit Ug Carrier Perth Fibre Conduit Ug Carrier Communication Pit 66kv Underground \bigvee **66kv Termination** 132kv Underground 132kv Termination 330kv Underground Retrospective Underground High Voltage Busbar H. V. Underground High Volt Single Phase Single Phase Underground Capacitor Bank Circuit Breaker Disconnector **Fuse Switch** Hv Cable Pole Termination Meterina Unit Non Load Break Connector Reactor **Surge Divertor Switch Disconnector** Low Voltage Busbar L. V. Underground Circuit Breaker Disconnector Disconnector, Underground Fuse Disconnector, Underground Lamp Lv Cable Pole Termination **Building Lines To 10000** Building Lines To 5000



3፻፵୭፻፻፮4"\$' (Zone 50): (39163081,644499377) Scale: 1:2500 Profile: #DBYD (Modified)

Cable Joint Ces Scheme Join Underground Easements Join **Water Feature** Tee Junction Oil Pipe Carrier Approximation Otc Underground Cable Lodged Centroids Data Overhead Data Underground Planned Subdivisions **Turquoise Precalc Centroids** Kiosk ****** L. V. Distribution Frame Turquoise Precalc Int Lot Boun **Turquoise Precalc Road Front** Pillar Ring Main Unit **Green Legal Centroids** Substation **Obsolete Centroids Underground Crossing** St. Lt. Pilot, Overhead St. Lt. Pilot, Underground Fuse Disconnector, Overhead St. Lt. Circuit, Overhead St. Lt. Circuit, Underground Distribution Pipe Link Pipe Trunk Pipe Bright Conduit Ug Carrier Perth Fibre Conduit Ug Carrier Communication Pit 66kv Underground \bigvee **66kv Termination** 132kv Underground 132kv Termination 330kv Underground Retrospective Underground High Voltage Busbar H. V. Underground High Volt Single Phase Single Phase Underground Capacitor Bank Circuit Breaker Disconnector **Fuse Switch** Hv Cable Pole Termination Meterina Unit Non Load Break Connector Reactor **Surge Divertor Switch Disconnector** Low Voltage Busbar L. V. Underground Circuit Breaker Disconnector Disconnector, Underground Fuse Disconnector, Underground Lamp Lv Cable Pole Termination **Building Lines To 10000** Building Lines To 5000

